

# INTEGRATED MEDICAL SERVICES

Avondale, Arizona



- This project is a total precast, 60,000 SF medical office building utilizing structural gray concrete with a smooth form finish which was then painted.
- The exterior wall panels are 14" thick vertical "E-shaped" components with an 8" deep recess around the window openings.
- Horizontal and vertical reveals emphasize the planning module on the buildings exterior and create more visual interest.



*Owner: Integrated Medical Services*

*Architect: Archicon LC*

*Engineer: TLCP Structural Engineers*

*General Contractor: IBC Southwest*

**CORESLAB  
STRUCTURES (ARIZ) INC.**

(602) 237-3875 • Fax: (602) 237-3459

E-mail: [salesarizona@coreslab.com](mailto:salesarizona@coreslab.com) • Visit us at: [www.coreslab.com](http://www.coreslab.com)